RRS Discovery







Colin Day NOC OFEG-TECH 2013

nttp://noc.ac.uk

James Cook & new Discovery Compared







	Cook	Discovery
Length Overall:	89.50 m	99.70m
Breadth:	18.60 m	18.0m
Draft:	5.50-5.70 m	6.50m
Displacement:	5368t GRT	6075T GRT
Class:	Lloyds +100A1, lce 1C, FS, +LMC, UMS, DP(AM) Research Vessel	Lloyds +100A1, Ice 1D, +LMC, UMS, IWS, EP, DP(AM), NAV1, IBS, Research Vessel
Maximum Speed:	15 kts SS4	15kts SS2
Cruising Speed:	12 kts SS4	12kts SS4
Maximum Endurance:	50 days	50 days
Science & Stores DW:	385T	380T
Scientific Berths:	32 singles	28 singles
Officers:	9 singles	12 singles
Crew & Technicians:	13 singles	12 singles
Open Deck Spaces (Afterdeck & Stbd Amidships):	446 m ²	432 m ²
Total Lab Areas:	277.5 m ²	388.8 m ²




RRS James Cook / Discovery Replacement Comparison



























RRS Discovery hydro graphic suite

		RRS Discovery			Comment on installation Issue
	Blister	Port drop keel	Stbd drop keel	Pole	
EM122 1° x 1° 12kHz MBES	٧				The RRS James Cook has an EM120 (hull mounted), the RRS Discovery has an EM122 blister mounted.
SBP120 3° x 3° sub-bottom profiler	٧				
EM710 2° x 2° 70-100kHz MBES	٧				EM710 moved to blister from the drop keel. More stable location.
75kHz ADCP	٧				On RRS James Cook the ADCPs acoustic path
150kHz ADCP	٧				could be obstructed by the starboard drop keel causing signal loss.
Hydrophone –(Acoustic background & system performance)	٧				New installation for the RRS Discovery
EA600 12kHz single beam sounder		V			
10kHz single beam echo sounder		V			Moved to port drop keel on RRS Discovery.
CCTV underwater camera		٧			New installation for the RRS Discovery
EK60 Bio echo sounder; 18kHz, 38kHz 70kHz, 120kHz, 200kHz, 333kHz			٧		Additional frequency transducers included on RRS Discovery
Scanmar S-1004/s-1007 hydrophone			٧		New installation for the RRS Discovery
Hydrophone – (background flow noise monitoring/system performance)			٧		New installation for the RRS Discovery
Ultra Short Base line (USBL)				٧	



Main Discovery over side handling systems – 20T starboard P-Frame





The starboard parallelogram handling system (P-Frame) is positioned fwd of the starboard 20T beam system. The P-Frame is designed to handle all the ships wires, cables and ropes.

The P-Frame geometry allows a package to be lifted off the starboard deck, over the bulwark with out using the winch.







Main Discovery over side handling systems – 20T Starboard beam





The starboard 20T beam handling system is positioned Aft of the starboard P-Frame system.

The beam is designed to handle all the ships wires, cables and ropes.

The beam can be fitted with a ROV handling frame with locking head







Main Discovery over side handling systems – 20T stern A-Frame



Stern 20Te A Frame:

Main central 20Te deployment block

4 auxiliary deployment points.

2 5Te auxiliary winches





Ship fitted winch systems





Ship fitted winch systems, wires, cables & ropes:

- 1. ROV / deep tow winch:
 - Traction winch
 - 12.5 Te maximum line pull
 - 2m/sec line speed
 - 10,000m steel armoured Electro-Optical cable (Rochester triple armoured, triple optic fibres, 3 copper core cable); MBL 20.9 Te
- 2. Standard steel CTD winch 1 & 2
 - Traction winch with 2 storage drums
 - 5 Te maximum line pull
 - 2m/sec line speed
 - 8,000m steel armoured Electro Mechanical 11.43mm cable; MBL 8.61 Te
- 3. General Purpose winch
 - Direct pull winch
 - 11 Te at mid layer line pull
 - 2m/sec line speed at mid layer
 - 7,000m 3x25 RHO steel rope; MBL 18.56 Te



Ship fitted winch systems, wires, cables & ropes:

- 4. Trawl winch -
 - Traction winch
 - 12.5Te maximum line pull
 - 2m/sec line speed
 - 15,000m tapered steel rope; MBL 13 Te / 18.1 Te / 20.9 Te
- 5. Coring winch
 - Traction winch
 - 20 Te maximum line pull
 - 2m/sec line speed
 - 8,000m synthetic Mechanical cable (Cortland 28mm 'Plasma' Dyneema); MBL 66.5 Te
- 6. Clean CTD winch
 - Direct pull winch
 - SWL 4 Te at mid layer, 3.7 Te outer layer
 - 2m/sec line speed
 - 2.4 m/sec with AHC (6m@8sec)
 - 8,000m synthetic rope (Cortland Vectran braided rope); MBL 9.9 Te / WL 1.32 Te



Acceptance trials

- A range of marine acceptance trials and shallow winch trials were carried out locally to Vigo between March and July 2013
- Following these acceptance trials the ship was officially handed over to NERC but a number of issues still remained outstanding
- Deep sea winch trials carried out in the N Atlantic in September 2013
 - Tests were carries out to prove:
 - General operation of the winches
 - 24 hour operational capability of the winches
 - Effectiveness of cable and rope runs, routes and sheaves
 - Effectiveness of spooling systems
 - Reliability of control systems and user interface
- Following these trials modification and repair work was identified
- A further deep sea winch trials is planned for January 2014
- Hydro graphic trials were carried out in the N Atlantic in October 2013 which proved to be very successful!



Future trials and science activities

- 2nd deep sea winch trials planned for January 2014 in the N Atlantic; sailing from Southampton to Lisbon.
- Dry dock planned for Vigo in February 2014 to carry out modification work.
- 1st science cruise planned for March 2013
- Guaranteed dry dock planned for the summer of 2014

